
International Flight Inspection Symposium


Oklahoma City, OK USA June 2008



Flight inspection of GNSS-based precision approaches to regional airports in Norway

Steinar Hamar Avinor AS






precision approaches

Hammerfest

70°39′




3 of 33



Flight inspection of GNSS-based precision approaches


Widerøe STOL-port operations in 2007



STOL-ports Summary

- Short runways (800 m)
- Non-precision step-down approaches
- High minima black hole effect
- Many circlings
- Turbulence & rapidly shifting inclement weather
- Long periods of winter darkness
- Uncontrolled, non-radar environment
- CFIT prone

CFIT Hazards – Grave Statistics



Two CFIT Accidents

May 6, 1988: Dash-7 flew into mountain – step-down fix missed

October 27, 1993: DHC-6 crashed before runway – black hole effect

CFIT Risk 10 to 15 times higher than for larger airports

Flight inspection of GNSS-based precision approaches

Total -135

Glide slope - DGPS - 'SCAT-1'

- Norwegian Parliament Mandate to install electronic glide slopes at STOL-ports (1996) following the CFIT accidents
- ILS GS?
 - Inadequate due to unique geographic features which makes conventional ILS GS impossible to install & operate
- Norwegian CAA Task Force Recommendation:
 - DGPS approaches at STOL-ports
 - Concept / Technology: SCAT-I

Four Party Team established


Avinor

- Project owner project management
- Universal Avionics Systems Corporation
 - Airborne equipment
- Raytheon (now: Park Air Systems)
 - Ground station
- Widerøe
 - Operator

DGPS - 'SCAT-I'

- Proof-of-concept (1997)
 - Used a Dash-8 with non-certifiable avionics and ground station
 - Very promising results
 - Benefits were clearly demonstrated to airline, service provider and regulators

The SCAT-I Concept



2001 Test Flights

- LN-ILS (Avinors Flight Inspection Aircraft) was equipped with:
 - 2 GLS 1250 GPS landing sensors from Universal
 - Glide slope truthing functions in Flight Inspection
 System (new SW for EL/AZ deviation)
- NM8005 SCAT-I Ground Station at Torp Airport
- Testflights were performed, accuracy evidenced and results declared very satisfactory
- Commercial Participants were determined to proceed with remaining development and certification efforts - future looked bright!


Certification stall – project dormant

- Late 90s saw many manufacturers leave SCAT-I for the greener grass on the LAAS side of the fence
- In 2001 FAA withdrew and it's LAAS Integrity Panel (LIP) was withdrawn from the program
- Program went dormant Avinor looked for other options
- Outcome of Dec 2003 high level meeting with FAA in DC:
 - FAA will do TSO and STC baseline certifications for the airborne equipment (LA ACO appointed)
 - N-CAA will do the type approval for the ground station
 - N-CAA's SCAT Integrity Panel (SIP) to work airborne and ground based systems

Memorandum of Understanding

 Meetings in FAA LA ACO's back yard in May 2004 produced a truly international "treaty" that obliged the participants to finalize developments and have the various elements of the SCAT-I concept certified within an agreed timeframe.


The resurrection



Certification Test Flights

- FAA and TC flight tests conducted at ENBN airport in May-05
- A total of 135 approaches were flown:
 - 2 aircrafts
 - LN-ILS with single FMS and truthing system
 - LN-WIN with double FMS
 - -3.9° (normal), 4, 4.5, 5 and 6° (steep)
 - Head-, cross- and tail- wind (autopilot /flight director/raw)
- All were successful no tunnel penetrations other than forced – accuracy unprecedented

The certification maze




Certifications

- All in all, it turned out that the SCAT-I program needed
 23 regulator approvals before the inauguration flight could take place on the 29th of October 2007
- The process took 11 years
- Three more regulator approvals are required before the Flight Inspection Unit, its equipment and the King Air B-200 aircraft is certified for SCAT-I flight inspection

GNSS Flight Inspection

- Prototype truthing functions were used in the 2001 tests
- An approved version of NFIS was needed for the certification flight tests and commissioning and recurring flight inspection evaluation
- Requirements for equipment upgrade were derived from
 - FAA Order 8200.41
 - Doc 8071 Vol.2
- Equipment to be capable of providing corrected aircraft position to a defined accuracy level
- For a GNSS based positioning system there must be no common mode errors between the positioning system and the system under test

Block Diagram of NFIS




Flight Inspection Requirements

- Commissioning Flight Inspection Evaluation
- VHF Data Link (VDL)
- Initial and Intermediate Approach Segments
- Final Approach Segment
- Missed Approach Segment
- Special Instrument Approach Procedure
- Confirming Flight Inspection
- Periodic Evaluation

Flight Inspection Procedures

- Program and procedures were developed to meet each and every requirement and with additional functions added:
 - Verification of automatic arming of FMS SCAT-I approach function
 - Establishment of approaches via all IAFs
 - Check of potential shadowing of GPS antennas
 - Verification of glide path tunnel position and flags
 - Flyability

SCAT-I Approach




NFIS in DCH-8 LN-ILS



Flight inspection of GNSS-based precision approaches

AZ, EL & VDL curves for one run



Calculated figures same run



NFIS Data Sample

UTC	REF	REF	AZ	EL	AZ	EL	AZ	EL	AZ	EL
HH:MM:SS	DIST	ALT	REF	REF	DEV	DEV	Tunnel	Tunnel	PEN	PEN
			DEG	DEG	FT	FT	FT	FT	%	%
08:42:21	3,4	1500	0,05	0,08	17,57	29,75	525	172	3	17
08:42:21	3,4	1498	0,05	0,08	17,56	29,74	524	172	3	17
08:42:21	3,4	1497	0,05	0,08	17,54	29,71	524	172	3	17
08:42:21	3,4	1496	0,05	0,08	17,88	29,68	524	172	3	17
08:42:21	3,4	1491	0,05	0,08	17,83	29,59	522	171	3	17
08:42:56	2,2	1000	0,04	0,02	9,77	5,00	358	117	3	4
08:42:56	2,2	999	0,04	0,02	9,75	5,23	358	117	3	4
08:42:56	2,2	998	0,04	0,02	9,74	5,22	358	117	3	4
08:42:57	2,2	996	0,04	0,02	9,72	5,45	357	117	3	5
08:42:57	2,2	995	0,04	0,02	9,71	5,68	357	116	3	5
08:44:01	0,4	205	0,02	-0,08	0,83	3,13	111	32	1	10
08:44:01	0,4	204	0,02	-0,09	0,86	3,17	111	32	1	10
08:44:01	0,3	203	0,02	-0,09	0,89	3,30	111	32	1	10
08:44:01	0,3	201	0,03	-0,09	0,92	3,34	110	32	1	10
08:44:01	0,3	200	0,03	-0,09	0,95	3,42	110	32	1	11

IFIS 2008, OKC

Flight inspection of GNSS-based precision approaches


Flight Inspection & Certifications

- The flight inspection system played a key role in the certification process for SCAT-I avionics and ground facilities.
- LN-ILS as testbed for base-line SCAT-I certification with the onboard NFIS provided real time data and a database for 100 runs (5 samples/sec) for post test analysis.
- Base-line avionics certification materialized quickly
- Operating approval of the Ground Facility called for another sequence of flight inspection encompassing the comprehensive program and procedures outlined earlier
- The flight inspection test results again provided a firm basis for the N-CAA operating approval that followed

Preparing for SCAT-I operations

- Criteria for procedure design (normal/steep/offset)
- Data generation and distribution process
- Phraseology
- Maintenance Guidelines
- Training requirements (ATC / AFIS / Pilots / Nav aid technicians)
- Availability prediction / NOTAM

Data generation and distribution



Implementation

Avinor

- Brønnøysund inaugurated in Oct 2007 (having been in trial operation for 6 years)
- Hammerfest operational July 3rd 2008
- 9 Ground Stations in various stages of implementation all up by end 2009
- 22-24 Ground Stations operational by end of 2011

Implementation

Widerøe

- Pilot training (350) in progress (simulator / line flying with supervisors)
- Aircraft upgrade (17) in progress
- Line flying on SCAT-I equipped airports continuously

Payback

We strongly believe that the persistent pursuit of certifying SCAT-I continuously over a period 11 years will finally pay off in precision approaches and significant improvement in flight safety for the STOL-ports and the pilots love to fly it!